




EXAMPLE SHOWN

NOTES:

MATERIAL
ALL DIMENSIONS REFERENCED IN NOTE IS IN INCHES
FACESTOCK: Low-gloss, white, vinyl film. Will caliper to .004 ±.0005.
ADHESIVE: Flexcon VI56 permanent bonding pressure-sensitive acrylic adhesive (min. thickness .0007 ±10%).
Suitable for bonding to an enamel painted steel or aluminum surface.
Minimum service temperature range shall be -20°C to +80°C.
OVERLAMINATE: Frosty clear vinyl or matte clear polyester. Will caliper .001 to .004 ±10%.
LINER: 40# to 60# (basis weight) removable, release coated paper liner.

COLOUR:
BACKGROUND: Pantone Process Yellow C.
TEXT AND GRAPHICS: Pantone Process Black C.
BLUE AREA ON LOWER IMAGE: COLOUR DEFINED IN ISO 7010-M002 PART 4

TO BE SUPPLIED ON ROLL

REFER TO ARTWORK FILES "C28747_ART" ON ECN 8569 FOR POSITION AND SCALE OF GRAPHICS AND PRINTING.
BLACK TEXT SIZE IS NOT CRITICAL BUT MUST BE READABLE / LEGIBLE

DRAWING NUMBER AS PER DRAWING BOARDER

SCALE	2.50 @ A3	R.F.E.A. 0
MATERIAL	SEE DWG	
DESCRIPTION	META O.R.v3	META
LABEL SAFETY ICONS		
DWG No	C32376	ISS. A
DRAWING SHEET 2 OF 2		