

| OCP Ready COLO Facility Assessment | Stockton 1 | | | |
|---|---|--|------------|-------|
| Self Assessment Status: | COMPLETE-MEETS REQUIREMENTS | | | |
| Data Center Location Name | Stockton 1 | | | |
| Data Center Location Address | 1002 Embarcadero Stockton, California 95203 | | | |
| Site Description: White Space Area | 10000 Sq ft | | | |
| Site Description: Critical IT Power | 7MW | | | |
| Site Description: Network Provider Availability | 100% | | | |
| Site Description: Facility Features | 2 acres with 300 linear ft of Water Front Berthing Space for Waterbourne Data Center | | | |
| Site Description: Other Services | Tier 1 Port- Port of Stockton Homeland Security | | | |
| Date Original Assessment is Completed | 5/27/2021 | | | |
| Re-Assessment Date: | | | | |
| REQUIREMENTS - Attribute (Must have an Optimum or Acceptable result) | Parameter | | Result | Notes |
| ACCESS | | | | |
| Building Access | 1. Loading dock with lift or leveler | | Optimum | |
| Delivery pathway, Loading dock to Goods in | 1. ≥2.7m (108in) H x ≥2.4m (96in) W x ≥2.4m (96in) D unobstructed access and threshold free | | Optimum | |
| Delivery pathway, Goods in to White space | 1. ≥2.4m (96in) H x ≥1.8m (72in) W unobstructed access and threshold free | | Optimum | |
| Corridor floor rolling load | 1. ≥680kg (1500lb) (6.67kN) | | Optimum | |
| Unboxing/pre-staging/storage area floor uniform load | 1. ≥1221kg/m2 (250lb/ft2) (11.97kN/m2) | | Optimum | |
| Unboxing/pre-staging/storage area floor concentrated load | 1. ≥680kg (1500lb) (6.67kN) | | Optimum | |
| RAMPS | | | | |
| Gradient | 1. Not Applicable - No Ramps Required | | Optimum | |
| Width | 1. Not Applicable - No Ramps Required | | Optimum | |
| Landing area | 1. Not Applicable - No Ramps Required | | Optimum | |
| Railings | 1. Not Applicable - No Railings Required | | Optimum | |
| LIFTS / ELEVATORS | | | | |
| Weight loading | 1. ≥1500kg (3300lbs) | | Optimum | |
| Door height | 1. ≥2.4m (96in) Lift /Elevator door opening height (not internal cabin) | | Optimum | |
| Width | 1. ≥1.5m (60in) Unobstructed door opening width | | Optimum | |
| Depth | 1. ≥1.5m (60in) Unobstructed cabin depth | | Optimum | |
| WHITE SPACE | | | | |
| Floor rolling load | 1. ≥680kg (1500lb) (6.67kN) | | Optimum | |
| Floor uniform load | 1. ≥1221kg/m2 (250lb/ft2) (11.97kN/m2) | | Optimum | |
| Floor concentrated load | 1. ≥680kg (1500lb) (6.67kN) | | Optimum | |
| Finished floor to ceiling height | 1. ≥4.5m (180in) | | Optimum | |
| Access floor clearance | 1. Not Applicable - No Access Floor | | Optimum | |
| ELECTRICAL | | | | |
| Number of independent circuits to the rack | 1. 2N (A+B) | | Optimum | |
| Maximum circuit capacity | 1. 3ϕ 60A/208V | | Optimum | |
| Circuit voltage | 1. 208 VAC Nominal | | Optimum | |
| Circuit frequency | 1. 47-63 Hz | | Optimum | |
| Power receptacle / WIP Type | 1. IEC60309 460R9W | | Optimum | |
| Circuit receptacle location | 1. Overhead | | Optimum | |
| Upstream UPS options | 2. UPS only feed available | | Acceptable | |
| Rack-based batteries permitted | 1. Allowed | | Optimum | |
| Generator load acceptance time | 1. <60 seconds | | Optimum | |
| COOLING | | | | |
| Rack airflow direction | 1. Front to Back | | Optimum | |
| Air containment methods | 1. Not Applicable - Rear Door Heat Exchangers (RDHx) Deployed (notes required) | | Optimum | |
| Maximum rack density | 1. ≥12kw | | Optimum | |
| Minimum cold aisle width | 2. ≥1200mm (48in) | | Acceptable | |
| Minimum free width cold aisle (Inside cage) | 1. ≥1200mm (48in) | | Optimum | |

| | | | |
|---|---|------------|---|
| Minimum hot aisle width | 2. ≥900mm (36in) | Acceptable | |
| Inlet air conditions | 1. ASHRAE Class A1 Allowable | Optimum | |
| Air quality | 1. EN 779 G4 and F7 filtering & Gas particulate monitoring to the ANSI/ISA 74.04-1985 G severity levels | Optimum | |
| Temperature rise | 1. ≥12 Deg C DeltaT | Optimum | |
| Cabinet blanking of open space | 1. Mandatory | Optimum | |
| CABLING | | | |
| Cabling infrastructure pathways | 1. Top and Front of rack fed | Optimum | |
| Overhead Network Infrastructure containment levels | 1. 3 Levels (Intra-Pod cabling; Inter-Pod cabling; OOB cabling) | Optimum | |
| Fibre Type (if installed) | 1. OS2 & OM4 | Optimum | |
| Fibre connection presentation (if installed) | 1. Interchangeable LC Duplex and MPO | Optimum | |
| CONSIDERATIONS (For information only) | Parameter | Result | Notes |
| SERVICE | | | |
| Replacement PSU Modules | 1. In stock onsite | Optimum | |
| Replacement BBU Modules | 1. In stock onsite | Optimum | |
| Option to monitor PSUs and BBUs | 1. Yes | Optimum | |
| Remote hands for PSU and BBU replacement or expansion | 1. Yes | Optimum | |
| Remote hands for OCP IT hardware replacement or expansion | 1. Yes | Optimum | |
| EFFICIENCY | | | |
| Site Operations Standards | 1. OCP Critical Facility Operations Guidelines | Optimum | |
| Site PUE Monitoring | 1. Continuously monitored | Optimum | |
| Site Design PUE | 1. <1.2 | Optimum | |
| Site Annualized PUE Current Achievement | 2. Other (Notes required) | Acceptable | Current loading below logical PUE measurement thresholds given recent opening |
| Site WUE Monitoring | 1. Continuously monitored | Optimum | |
| Site CUE Monitoring | 1. Continuously monitored | Optimum | |
| OPENNESS | | | |
| PUE Published | 1. Real-time available online | Optimum | |
| Facility Design Drawings & Files | 2. Available to view upon request | Acceptable | |