

OPEN.



FOR
BUSINESS.



OCP
SUMMIT



Networking

Journey to the West: Integrating Cisco IOS-XR with OCP Technologies

Akshat Sharma, Technical Marketing Engineer,
Cisco Systems Inc.

OPEN. FOR BUSINESS



Journey to the West

- 16th Century Chinese novel and folklore by Wu Cheng-en.
- An extended account of the original “Journey to the West (India)” by Xuanzang in the 6th Century AD
- Led to **Neo-Confucianism**
a creative reinterpretation of the traditional Confucian core to meet new intellectual and spiritual expectations, intrinsically shaping the Chinese culture for years to come.






Networking

IOS-XR's “Journey to the West”: Incremental Disaggregation



OPEN. FOR BUSINESS




Disaggregating the Software Layers:



Disaggregating the HW from the SW:



Disaggregating the stack, one use case at a time






Networking

The Road to HW-SW Disaggregation for IOS-XR

OPEN. FOR BUSINESS



Integration Architecture:



Decision Stages: Selecting the Hardware

The Network integrator may choose the Hardware based on :

- Port Density
- ASIC and Platform capabilities


Typically, being OCP compliant will plug the platform into the ecosystem: with platform modules pushed to the ONL (Open Network Linux) git repo:

(<https://github.com/opencomputeproject/OpenNetworkLinux>) for example.




Decision Stages: Integrating with the Platform

- Typically Platform capabilities are exposed through modules published in the ONL git repo (<https://github.com/opencomputeproject/OpenNetworkLinux>)
- These modules usually get integrated as kernel modules into the NOS.
- The capabilities can be exposed to the higher layers of the stack either through
 - ONLP (Open Network Linux Platform) Abstraction layers (See <https://opennetlinux.org/docs/porting>)
 - Directly hooking the NOS abstraction layers with the kernel /sys/fs paths exposed by the modules.



Decision Stages: Integrating with the ASIC

- The ASIC SDK comes from the ASIC vendor. This may be licensed (either by the integrator or Software vendor).
- The ASIC SDK may also be exposed as an Open API:
For example, Broadcom provides an Open API on top of their SDK called [OpenNSL](#) for integration with a Hardware Abstraction Layer (HAL) in the NOS.



Decision Stages: Creating an Installer image

- Currently the OCP ecosystem utilizes ONIE as the image installation/bootloader paradigm.
- The required IOS-XR image is packaged up into an ONIE compatible installer image
- Whitebox devices can then download and install IOS-XR image via a DHCP server.





Networking

Cisco and the OCP

OPEN. FOR BUSINESS



Working with the OCP Community:

Leveraging the current ecosystem

- Currently IOS-XR Leverages the Vendor Modules published in the ONL Git repo
(<https://github.com/opencomputeproject/OpenNetworkLinux>)
- The Vendor module capabilities are directly integrated into IOS-XR through /sys/fs paths.
- The ONLP "write" capabilities such as handling fan speeds based on temperature sensor data (specific to platform) are leveraged.
- Great Documentation for individual projects such as ONIE, ONLP.



OPEN
Compute Project

Supported Hardware?

- We are working on Platform enablement on a case-by-case basis.
- Selection of Hardware is an important decision stage driven by Customers (operators and/or Network Integrators)
- As part of this process, currently enabled platforms by End of 2018:

- Edgecore AS5916-XKS : OCP-ACCEPTED™
- Edgecore AS7816-64X : OCP-ACCEPTED™

- More integrations planned based on customer requirements



Can we Play with IOS-XR on OCP-ACCEPTED hardware already?

- Limited availability (LA) of IOS-XR on supported third-party hardware for **select** customers towards the end of 2018.
- If you'd like to be involved, get in touch with your nearest friendly Cisco Systems Engineer (SE)/ Account Manager (AM)
- General Availability (GA) of IOS-XR on supported third-party hardware around Mid-2019
- For any other questions, requirement discussions, contact us at:
xrwb-external@cisco.com



Demo time!

OPEN. FOR BUSINESS



Working with the OCP Community:

Our Learnings

- **Enhancements to optics drivers** - especially in supporting newer optics, some minor API enhancements
- **Events from ONLP** : Currently everything is based on polling
- **Uniformity in platform data from BMC**: varies across vendors
- **Test scripts for ONLP?**



OPEN
Compute Project



OCP
SUMMIT

OPEN.



**FOR
BUSINESS.**

