



**OCP**  
SUMMIT

October 1-2  
**2018**  
Amsterdam

**OPEN. FOR BUSINESS**



# Project Cerberus Hardware Security

Bryan Kelly / Principal Firmware Eng Manager

Microsoft Azure Cloud Hardware Infrastructure

Yigal Edery / Principal Program Manager

Microsoft Azure Security

**OPEN. FOR BUSINESS**



**OCP**  
SUMMIT



# Talk Outline

- Firmware Security for the Cloud
- Current State of the Industry
- Project Cerberus deconstruct
- Open Compute Security Project

# OCP Security Context

*“Rogues are very keen in their profession, and know already much more than we can teach them” -- Alfred Charles Hobbs, 1851*

Open Compute Security Project was announced in February 2018

Microsoft and Google selected to serve as co-chairs, many companies contribute

Community focused on advancing platform hardware and firmware security

# The Firmware Security Challenge...



- BIOS
- BMC
- NIC
- FPGA
- SSD
- Option ROMs
- GPU's
- HBA's
- Etc...

*If you Own the firmware,*

*...You Own the server,*

*And you Own the cloud...*

*...And no one will find you...*

# The Hardware Threat is real !




Gives attackers full control

Getting weaponized (read: easy)



Hard to detect


Hard to remediate



# The Cloud Firmware Threat Vectors

## Vectors:

- **Internet** (Compromised customer, or malicious)
  - Hypervisor compromise
  - Bare Metal Services
- **Insiders** (Compromised or malicious)
  - Logical & physical access to hardware
- **Supply Chain**
  - Source of hardware



# So, what can an attacker do?

## Exploit a run-time firmware vulnerabilities

- Firmware **quality** is critical (reduce chances of run-time exploitability)
  - Follow secure development practices & Issue security updates with a proper SLA
- Assume breach and implement **defense In depth**
  - Component compartmentalization & limit the damage & reach of possible breaches

## Persist rogue firmware

- Modify firmware to maintain 'hold' of the breached hosts (Survive even formats and OS re-installs)
- Servers need the ability to protect, detect and recover from such attacks
- This is what Cerberus is all about...

# NIST 800-193 : Protect, Detect, Recover




Authenticate integrity of all firmware updates  
Root(s) of trust & chain(s) of trust across the platform



Detect unauthorized access or corruption  
Generate traces & events to help detect anomalies



Restore firmware to state of integrity  
Automatic, Automatable and manual recovery scenarios



<https://downloads.cloudsecurityalliance.org/assets/research/firmware/firmware-integrity-in-the-cloud-data-center.pdf>


# The Current State of Industry Servers

Fully Secured

Partially Secured

Not Secured

- **UEFI** – limited protection
  - Secure-boot-like functionality
  - No Detect or Recover
  - Platform dependent
- **BMC** - typically unsecure
  - No protect, no detect, no recover
  - No reliable attestation
  - E.g. [BlackHat Talk](#)
- **Peripherals** - Ad-hoc, usually limited
  - No protect, detect, recover
  - Not chained to platform RoT




# Introducing Project Cerberus

- 1 A set of **platform requirements**
  - E.g. Power sequencing while establishing trust
- 2 A set of **requirements** for ensuring **firmware integrity**
  - E.g. how to verify firmware integrity at boot
  - E.g. how to verify firmware signatures during updates
- 3 A **chip** that helps you implement the requirements

# What is the Cerberus Chip?

- Dedicated security microprocessor
  - Internal Secure SRAM, Flash.
- Contains crypto acceleration blocks
  - SHA / AES / TRNG / PKA
- Interpose SPI/QSPI filter interface
- e-fuses for authentication public key hash and manifest revocation
- Hardware Physically Unclonable Function (PUF)
- Device Identifier Composition Engine (DICE)
- Tamper resistance


# Interpose Interface



- All Firmware Authenticated
- All Firmware Measured
- All SPI Transactions Filtered
- All Region Access Controlled
- NIST 800-193 Enforced (Protect, Detect, Recover)


# Protection

- Runtime: All flash accesses filtered through Cerberus
- Enforces region protection.
- Authenticated updates only
- Maintains Platform Firmware Manifest (PFM) for digital signature verification




# Detection

- Pre-boot: Firmware integrity with digital signature enforcement
- Pre-boot attestable Firmware measurements, with freshness seed.
- Post-boot firmware integrity checks
- Post-boot attestable Firmware measurements with freshness seed.




# Recovery

- Policy based Recovery
- Bare-metal recovery images locked in flash
- Flash access protected by Cerberus
- Automatic recovery workflow on detection of corruption



# Platform Trust Hierarchy

- Scalable security architecture
- Motherboard contains master RoT.
- Each peripheral has a slave RoT capabilities interposed or native
- NIST 800-193 principles enforced at each level
- Master attests to platform firmware integrity



# Open Compute Security Project

- Charter & doc links : <https://www.opencompute.org/wiki/Security>
  - In a nutshell : Creating open specs for ensuring firmware integrity of an OCP platform
- Current areas of focus (working on specs)
  - Scoping the security threats
  - SecureBoot
  - Attestation
- Haven't started yet
  - Secure Updates
  - Recovery
  - Hardware interfaces
- We meet weekly. You're welcome to join!

# Key Takeaways

- Cerberus is Microsoft's RoT for Hardware
  - Implementation & designs open sourced to OCP
- You're welcome to join the OCP Security workgroups
  - We can use your help!
- Don't forget that firmware integrity is not the whole story
  - Firmware **quality** & **defense in depth** are critical too



**OCP**  
SUMMIT

October 1-2  
**2018**  
Amsterdam


**OPEN. FOR BUSINESS**

# Cerberus Deconstruct

- Power on sequence
- Cerberus boot
- Cerberus attestation
- Platform boot
- Platform attestation
- Cerberus Provisioning


# Power-On Sequence

- When power is applied, Cerberus powers first!
- Cerberus holds CPU and BMC in reset, they cannot access flash so holding them in reset is just a graceful thing to do.
- After Cerberus completes BMC flash digital signature verification, it allows flash access and releases reset.
- Cerberus communicates with peripherals for attestation measurements.
- After Cerberus completes BMC flash digital signature verification, it allows flash access and releases reset.




# Cerberus Boot

- Immutable ROM authenticates key manifest (mutable code).
- ROM selects key from Manifest and authenticates RIoT Core layer.
- ROM calculates CDI of Manifest and RIoT Core
- ROM launches and passes control to RIoT Core, passing CDI.
- RIoT Core selects key from Manifest and authenticates Cerberus application firmware.



# Cerberus Boot Continued (RIoT Core)

- ROM calculates CDI using Manifest and RIoT Core measurement
- ROM passes CDI to RIoT Core
- RIoT Core generates asymmetric Device ID key from CDI and Alias key from CDI and digest form FSD of Cerberus FW.
- Device Id Public key is provided to Cerberus Application Firmware
- Device Id Certificate and Alias Certificates are generated
- Alias Certificate is signed by Device Id key.
- If Device Id Certificate has not been signed, CSR is generated resulting in Device Id Certificate being CA signed during provisioning.




# Cerberus - Platform Firmware Manifest (PFM)

- Describes firmware attributes of protected device:
  - RO flash descriptor offsets
  - RW flash descriptor offsets
  - Versions and version index
  - Digest of code blocks
  - Public Certificate for verification
- Cerberus uses PFM to verify flash content
- PFM describes supported firmware images.
- PFM is a signed update to Cerberus application firmware.

```
<Firmware version="1.01.0">
  <VersionAddr>0x00FF004B</VersionAddr>
  <ReadWrite>
    <Region>
      <StartAddr>0x00EA0000</StartAddr>
      <EndAddr> 0x00FEFFFF</EndAddr>
    </Region>
  </ReadWrite>
  <SignedImage>
    <PublicKey>
      -----BEGIN PUBLIC KEY-----
      MIIBIjAIAhDNzXoifD6yQEFAAOIMAhDNzXoifD6yQEAx+Y05PThU4AbodORMVLj
      JNZZFB99bsW9oUx+U4Ugfrrog//kf825xzKedZIMAIMAhDNzXoifD6yX0IMAhDN
      8E+8nQesKthivc72IMAhDNzXoifD6y1VGBol/MvIMAhDNzXoifD6y0syy+/2Ke16
      1yFMKcmWfH8IMAhDNzXoifD6yZmJzFiEy4Bnas+npwWTIxmCWrAn7uQsyPfyTgs
      E3M8r115B0u517pA/SEIMAhDNzXoifD6yM0QmOkAJA+vkWwyx1U1X/sm2cqbBeK
      v9N+P5DpnpZXVWxb/BuC8Gk16iDEFWm/dcoOzIMAhDNzXoifD6yEYVNBcjQUL106
      ZQIDAQAB
      -----END PUBLIC KEY-----
    </PublicKey>
    <Signature>
      8e5c726fb6b8e5c726fb6bb4e32afcaaa1078cfe00b1ec31d82b530e16
      7f4a6d953bef1563a2272a4b63eedeeb32b3beb4e2caedf027fd95f086c5
      e048d62e015f48e5c726fb6bbr999c931d7c46a4d6b87d7a7739a9461eb1
      fc652a2e1ba3dcd69832e9c16ba90944ac799883b1e0a1f2f16763330d03
      2d46f7d9892d5739f78e5c726fb6b6893a8e5c726fb6bb2c538621f5baf6
      39191dbf5e593a93fa2b417750fbd6b997f25d268e5c726fb6bbdaeff601
      2bcca3338a2b8e5c726fb6bbb308e5c726fb6bbc4aa1b7f632d58e5c7269
      66a810e41cd6563b0139cd8e5c726fb6bb6fb6bb9618c0a8e5c726fb6bb2
      3c727dbd148e5c726fb6bb8806668733
    </Signature>
  </Region>
  <StartAddr>0x00000000</StartAddr>
  <EndAddr>0004FFFF</EndAddr>
</Region>
<Region>
  <StartAddr>0x00050000</StartAddr>
  <EndAddr>0x00C4FFFF</EndAddr>
</Region>
<Region>
  <StartAddr>0x00C50000</StartAddr>
  <EndAddr>0x00E9FFFF</EndAddr>
</Region>
<Region>
  <StartAddr>0x00FF0000</StartAddr>
  <EndAddr>0x00FFFFFF</EndAddr>
</Region>
  <ValidateOnBoot>true</ValidateOnBoot>
</SignedImage>
</Firmware>
```


# Cerberus - BMC Verification

- PFM describes FW digest structure
- PFM declares read-only, read-write regions
- Cerberus verifies digital signature of image on flash matches PFM
- Measurement extended for attestation.
- Cerberus SPI filter enforces runtime region protection
- Flatten Image Tree (FIT) permitted for secure boot extending.
- UEFI and other components protected in the same way.




# Cerberus - BMC Golden Recovery

- Cerberus detects image integrity corruption
- If BMC restored from backup flash
- Always recoverable, Cerberus can internally stores BMC recovery uboot.
- Golden uboot performs NFS FIT secured Linux boot




# Revocation

- Platform Firmware Manifest (PFM) are forward only.
  - PFM ID defined as uint64, does not permit rollback.
- PFM enforcement is function of the Cerberus firmware.
  - Soft revocation
- PFM is signed with key from key manifest.
- Key manifest can be hard revoked, using OTP memory and manifest ID



# Cerberus Attestation Policies

- In-band attestation
  - SPI to Cerberus
  - KCS bridged through BMC to Cerberus
- Out Of Band (OOB) attestation
  - Ethernet bridged through BMC to Cerberus
- Policies can be set on Cerberus for remediation
  - Recovery
  - Power Control



# Cerberus – Security Controller


Guided by NIST, enforces firmware integrity  
Protection, Detection and Recovery.

Cryptographic microcontroller enforces digital  
signatures on all platform firmware modules.

Hierarchical Root-of-Trust topology, provides  
attestation for all firmware modules

Opened the design

Security Project Committee in OCP



# Open Compute Project

- Founded in April 2011 by Facebook
- Microsoft joined in January 2014
  - Shared collateral for Open Cloud Server
  - Optimized for cloud scale and density
  - Contributed design was fully complete ☹️
- October 2016 Microsoft announced Project Olympus
  - Design was 70% complete
  - Attempting Open Source Server Hardware
- Community contributed to the design taking it to 100% complete – something never attempted before in OCP.



Open Cloud Server



Project Olympus

# Project Olympus

- Community feedback incorporated into the solution
- System and Rack design
- Manufacturing collateral schematics and board files open sourced
- Open Firmware: Open EDKII, OpenBMC and Open PDU and Rack Manager



# Open Source Momentum. . .




# More Open Building Blocks Followed

Flash Storage



HDD Storage



GPU / PCIe

